

MDT Switch Actuator AMI



MDT Switch Actuator 4/8/12-fold with current measurement, MDRC

Version				
AMI-0416.03	Switch Actuator 4 fold	4 SU MDRC, 16/20 A, 230 V AC, C-load, industry, 200 μF, current measurement		
AMI-0816.03	Switch Actuator 8 fold	8 SU MDRC, 16/20 A, 230 V AC, C-load, industry, 200 μF, current measurement		
AMI-1216.03	Switch Actuator 12 fold	12 SU MDRC, 16/20 A, 230 V AC, C-load, industry, 200 μF, current measurement		

The channels of the MDT switch actuator are switched independently of each other via bistable relays. Manual operation is possible via the buttons on the actuator.

Each output can be individually programmed via the ETS. Logical links, threshold functions, status feedback, lock functions, central switching functions as well as comprehensive time functions such as on/off delays and staircase lighting functions are available for selection. Scene functions are also available.

The switch actuator enables current measurement per channel as well as measurement of the total current. Depending on the setting, the measured values can be sent to the KNX bus in different data formats (mA / A / W / kW). In addition, the actuator has an operating hours meter / service count down timer. The energy consumption (Wh / kWh) can be measured with the integrated meter function. The power is calculated via a factor to be set from voltage and $\cos \phi$. In the event of a mains voltage failure, all relays maintain their current switching position. In the event of a bus voltage failure or a return, the switching positions of the relays can be programmed individually for each channel.

The switch actuator is intended for fixed mounting on a 35 mm DIN rail in power distribution in dry indoor spaces.

The MDT switch actuator is commissioned using the ETS software.

The product application is available at www.mdt.de/downloads.html and in the ETS online catalogue.

AMI-0416.03



AMI-0816.03



- Comprehensive application
- Integrated True RMS current measurement (current, kWh)
- Current measurement range 10 mA to 20 A
- Integrated energy consumption meter function (Wh / kWh)
- Fast reaction < 1 s at Master/Slave operation
- Push Button for manual operation and LED indicator for each channel
- Time functions (switch-on/switch-off delay, staircase light function)
- Threshold switch function and Consumption threshold value
- Logical linking of binary data, 8 scenes per channel
- · Operating hours meter
- Extended status functions (inverted, cyclic, when locked)
- Priority / forced operation with automatic release time
- Adjustable behaviour on bus voltage failure / -return
- All L-connections separated,
 4 mm² / 2 x 2,5 mm² connection terminals



MDT Switch Actuator AMI



Technical data	AMI-0416.03 AMI-0816.03 AMI-1216.03			
Number of outputs	4	8	12	
Current measurement range		10 mA 20 A		
Measurement inaccuracy		2 %		
Sampling rate	2000 Measurements / 500 ms			
Output switching ratings				
Ohmic load	16/20 A *			
Capacitive load		200 μF		
Voltage		230 V AC		
Maximum inrush current	600 A / 150 μs 300 A / 600 μs			
Maximum lamp loads				
Incandescent lamps		3680 W		
Halogen lamps 230 V	3680 W			
Halogen lamps, electronic transformer		2000 W		
Fluorescent lamps, not compensated		3680 W		
Fluorescent lamps, parallel comp.		2500 W		
max. number of electronic transformers	28			
Output life expectancy (mechanical)	1.000.000			
Total current carrying capacity	64 A	96 A	128 A	
Specification KNX interface	TP-256 with long frame support from ETS 5			
Available application software	From ETS 5			
Permitted wire gauge				
Screw terminal	1 × (0,5 4,0 mm²) 2 × (0,5 2,5 mm²)			
KNX bus connection terminal	Ø 0,8 mm, solid core			
Torque screw terminal	0,5 Nm			
Power supply	KNX bus			
Power consumption KNX bus typ.	< 0,3 W	< 0,4 W	< 0,4 W	
Operation temperature range		0 °C +45 °C		
Enclosure		IP20		
Dimensions MDRC (Space Units)	4 SU	8 SU	12 SU	

^{*} The total current of outputs next to each other is max. 32 A.

Example of connection AMI-0816.03

